


RACO 4" SQUARE BOXES - DRAWN - 1-1/4" Deep with Conduit KO




185



Description	Cat. No.	Average Cost	Suggested Resale	LABOR HOURS			
				(0-6')	(6-10')	(10-15')	(15-20')
1/2" KO	185	1.42	10.95	0.10	0.12	0.15	0.17

Description	Comparative 4" Square Boxes - 1-1/4" Deep w/Conduit KO			
	Appleton	Bowers	Steel City	Thepitt
1/2" KO	4SL-1/2	4-SS-1/2	52141-1/2	TP408

RACO 4" SQUARE BOXES - 1-1/2" Deep with Armored Cable Clamps




213




Description	Cat. No.	Average Cost	Suggested Resale	LABOR HOURS			
				(0-6')	(6-10')	(10-15')	(15-20')
1/2" KO	213	1.74	12.25	0.10	0.12	0.15	0.17
FH, Flush	219	2.02	16.50	0.10	0.12	0.15	0.17
B, Flush	224	1.94	17.25	0.10	0.12	0.15	0.17
FM, Flush	218	1.93	13.10	0.10	0.12	0.15	0.17

Description	Comparative 4" Square Boxes - 1-1/2" Deep w/AC Clamps			
	Appleton	Bowers	Steel City	Thepitt
1/2" KO	4SX	4-SW-MXN	52151-X	TP454
FH, Flush	4SXAB	-	52151-VX	TP461
B, Flush	4SXB-PL	4-SW-LB-MXN	52151-BX	TP456
FM, Flush	4SXVB-PL	4-SW-FB-MXN	52151-CVX	-



224

RACO 4" SQUARE BOXES - WELDED - 1-1/2" Deep with Conduit KO




181



Description	Cat. No.	Average Cost	Suggested Resale	LABOR HOURS			
				(0-6')	(6-10')	(10-15')	(15-20')
1/2" KO	189	0.88	9.15	0.10	0.12	0.15	0.17
3/4" KO	181	0.74	8.00	0.10	0.12	0.15	0.17

Description	Comparative 4" Sq Welded Boxes - 1-1/2" D w/Conduit KO			
	Appleton	Bowers	Steel City	Thepitt
1/2" KO	4S-1/2	4-SW-1/2	-	-
3/4" KO	4S-3/4	4-SW-3/4	52151-3/4W	-

RACO 4" SQUARE BOXES - DRAWN - 1-1/2" Deep with Conduit KO



190



Description	Cat. No.	Average Cost	Suggested Resale	LABOR HOURS			
				(0-6')	(6-10')	(10-15')	(15-20')
1/2" KO	190	0.76	6.80	0.10	0.12	0.15	0.17
3/4" KO	191	0.74	7.70	0.10	0.12	0.15	0.17
1/2" & 3/4" KO	192	0.59	6.90	0.10	0.12	0.15	0.17

Description	Comparative 4" Sq Drawn Boxes - 1-1/2" Deep w/Conduit KO			
	Appleton	Bowers	Steel City	Thepitt
1/2" KO	4S-1/2-DR	4-S-1/2	52151-1/2	TP410
3/4" KO	4S-3/4-DR	4-S-3/4	52151-3/4	TP412
1/2" & 3/4" KO	4S-SPL-DR	4-S-SPL	52151-1/2&3/4	TP414